# **Toole**DesignGroup



# APS Stratford Project Transportation Analysis Overview

BLPC #20 February 22, 2016

### Outline



- 1. Key Takeaways
- 2. TIA
  - A. Document
  - B. Analysis
  - C. Assumptions
  - D. Results—Key
  - E. Results—AM
  - F. Results—PM
- 3. Key Takeaways



# 3. Key Takeaways



#### **Arrival Peak Hour**

#### Both Site Plan and Alternate Site Plan

- 5-Points—Need signal timing changes. Need to extend southbound left-turn lane on Military on approach to 5-Points. NEW
- Old Dominion & Lorcom—Need signal timing changes. Do not need second northbound thrulane. NEW

#### Site Plan

Drop-off/Pick-Up driveway at Old Dominion—2 exit lanes needed. CONFIRMED

#### Alternate Site Plan

Drop-off/Pick-up driveway at Vacation—2 exit lanes needed. NEW

# 1. Key Takeaways

### Dismissal Peak Hour

Minimal impacts to vehicle operations.
 CONFIRMED

### **Old Dominion Signal Warrants**

Site Plan (Road)

 Full signal at new driveway exit meets warrants. CONFIRMED

Alternate Site Plan (No Road)

 Pedestrian Hybrid Beacon (HAWK) meets warrants. CONFIRMED

#### Site Plan vs. Alternate Site Plan

 TDG has no significant reservations about either the Site Plan or Alternate Site Plan from a transportation perspective.

#### **CONFIRMED**



### 2A. TIA Document



- Posted on APS website
- Includes:
  - Background information
  - Analysis of existing conditions
  - Trip generation
  - Site traffic distribution and assignment
  - Analysis of future conditions without development
  - Analysis of future conditions with development
  - Conclusions
  - Appendices


# 2B. TIA Analysis

### What we analyzed ...

- Vehicular delay--all study intersections
- Level of Service (LOS)—all study intersections
- Queueing—all study intersections and Vacation Lane

### **Analysis tools**

- SimTraffic used for unsignalized intersections.
- Synchro used for signalized intersections (including 5-Points).




**Study Intersections** 

# 2B. TIA Analysis



# How TIA analysis differs from previous analysis...

- Includes future year of 2019 (previously 2021) based on VDOT requirements
- Refined analysis of 5-points
- Revised trip distribution
- Analyzed impact of pedestrian crossings
- Included HAWK in Alternate Site Plan Analysis



Example of SimTraffic simulation




#### **Arrival**

- 35% drive rate
- 804 trips
- Trip distribution
  - Inbound Generally evenly distributed
  - Outbound Weighted slightly towards DC
- 2019 analysis year


#### **Dismissal**

- 22% drive rate
- 505 trips
- Trip distribution
  - Inbound Weighted slightly toward DC
  - Outbound Generally evenly distributed
- 2019 analysis year











#### **Trip Generation**

	AM Peak Hour Trips	PM Peak Hour Trips
Student Drop Offs	706	438
Staff	62	31
Visitors	10	10
Buses	26	26
TOTAL	804	505

# 2D. TIA Results—Key


Level of Service Codes





**Site Plan** 

Scenario Codes






Alternate Site Plan

### 2E. TIA Results – AM

### Average Delay per Vehicle (unit: Seconds)




### 2E. TIA Results – AM

### Average Delay per Vehicle (unit: Seconds)




# 2E. TIA Results—AM






## 2E. TIA Results—AM





### 2F. TIA Results – PM

### Average Delay per Vehicle (unit: Seconds)



### 2F. TIA Results - PM

### Average Delay per Vehicle (unit: Seconds)



# 3. Key Takeaways



#### **Arrival Peak Hour**

#### Both Site Plan and Alternate Site Plan

- 5-Points—Need signal timing changes. Need to extend southbound left-turn lane on Military on approach to 5-Points. NEW
- Old Dominion & Lorcom—Need signal timing changes. Do not need second northbound thrulane. NEW

#### Site Plan

Drop-off/Pick-Up driveway at Old Dominion—2 exit lanes needed. CONFIRMED

#### Alternate Site Plan

Drop-off/Pick-up driveway at Vacation—2 exit lanes needed. NEW

## 1. Key Takeaways

#### **Dismissal Peak Hour**

Minimal impacts to vehicle operations.
 CONFIRMED

### **Old Dominion Signal Warrants**

Site Plan (Road)

 Full signal at new driveway exit meets warrants. CONFIRMED

Alternate Site Plan (No Road)

 Pedestrian Hybrid Beacon (HAWK) meets warrants. CONFIRMED

#### Site Plan vs. Alternate Site Plan

 TDG has no significant reservations about either the Site Plan or Alternate Site Plan from a transportation perspective.

#### **CONFIRMED**



# Questions?

